


AD-A092 975


ARNOLD ENGINEERING DEVELOPMENT CENTER ARNOLD AFS TN F/G 20/4  
STATIC FORCE TESTS OF THE AEDC-VKF STANDARD 5 DEGREE CONE IN TU--ETC(U)  
SEP 79 J T BEST  
AEDC-TSR-79-V51

UNCLASSIFIED

NL


1 1 1 1  
AD-A092 975





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963 A

AEDC-TSR-79-V51




AD A092975

DOC FILE COPY

STATIC FORCE TESTS OF THE AEDC-VKF STANDARD  
5 DEGREE CONE IN TUNNEL A AT  
MACH NUMBERS 1.5 TO 4.0

J. T. Best  
ARO, Inc.



September 1979

Final Report for Period April 30 to August 1, 1979

Approved for public release, distribution unlimited.

**ARNOLD ENGINEERING DEVELOPMENT CENTER  
ARNOLD AIR FORCE STATION, TENNESSEE  
AIR FORCE SYSTEMS COMMAND  
UNITED STATES AIR FORCE**

80 12 17 037

#### NOTICES

When U. S. Government drawings, specifications, or other data are used for any purpose other than a definitely related Government procurement operation, the Government thereby incurs no responsibility nor any obligation whatsoever, and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise, or in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

References to named commercial products in this report are not to be considered in any sense as an indorsement of the product by the United States Air Force or the Government.


#### APPROVAL STATEMENT

This report has been reviewed and approved.

ERVIN P. JASKOLSKI, Capt. USAF  
Test Director, VKF Division  
Directorate of Test Operations

Approved for publication:

FOR THE COMMANDER

  
JAMES D. SANDERS, Colonel, USAF  
Director of Test Operations  
Deputy for Operations

9 Final report 30 Apr 1-1 Aug 79  
UNCLASSIFIED

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER 14 AEDC-TSR-79-V51	2. GOVT ACCESSION NO. AD-A092975	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) 6 Static Force Tests of the AEDC-VKF Standard 5 Degree Cone in Tunnel A at Mach Numbers 1.5 to 4.0.		5. TYPE OF REPORT & PERIOD COVERED Final Report, April 30 to August 1, 1979
7. AUTHOR(s) 10 J. T./Best/ ARO, Inc., a Sverdrup Corporation Company		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Arnold Engineering Development Center/DOOV Air Force Systems Command Arnold Air Force Station, TN 37389		8. CONTRACT OR GRANT NUMBER(s) 12 45
11. CONTROLLING OFFICE NAME AND ADDRESS Arnold Engineering Development Center/DOS Air Force Systems Command Arnold Air Force Station, TN 37389		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Program Element 65807F
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE 11 September 1979
		13. NUMBER OF PAGES 41
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Available in Defense Technical Information Center (DTIC)		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) aerodynamic forces      boundary layer trips standard 5 deg cone      Reynolds number base pressures supersonic flow		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Static stability and base pressure tests were conducted on the Arnold Engineering Development Center (AEDC) von Kármán Gas Dynamics Facility (VKF) standard force cone. The tests were performed at nominal Mach numbers of 4.0, 3.75, 3.25, 3.0, 2.75, 2.5, 2.25, 2.0, 1.75, 1.63, and 1.5 at free-stream unit Reynolds numbers ranging from $0.6 \times 10^6$ per foot to $3.7 \times 10^6$ per foot. The angle-of-attack and angle-of-sideslip ranges were from -11 to 11 deg. Configuration variables were nose bluntness and fins. The effects on static force		

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
84

data of the following were obtained: tunnel-nozzle jack setting errors, tunnel-flow humidity, and tunnel-sidewall misalignment.

**Accession Slip**

DATE RECEIVED \_\_\_\_\_  
BY \_\_\_\_\_  
FOR \_\_\_\_\_  
FROM \_\_\_\_\_

RECEIVED  
☐  
☒  
☐

**A**

**UNCLASSIFIED**

## CONTENTS

	<u>Page</u>
NOMENCLATURE . . . . .	2
1.0 INTRODUCTION . . . . .	5
2.0 APPARATUS	
2.1 Test Facility . . . . .	5
2.2 Test Article . . . . .	6
2.3 Test Instrumentation . . . . .	6
3.0 TEST DESCRIPTION	
3.1 Test Conditions and Procedures	
3.1.1 General . . . . .	6
3.1.2 Data Acquisition . . . . .	8
3.2 Data Reduction . . . . .	8
3.3 Uncertainty of Measurements . . . . .	9
4.0 DATA PACKAGE PRESENTATION . . . . .	9

## APPENDIXES

### I. ILLUSTRATIONS

#### Figure

1. Tunnel A . . . . .	11
2. Model Details . . . . .	12
3. Boundary Layer Trip Details. . . . .	14
4. Installation Sketches . . . . .	16
5. Tunnel A Nozzle Jack Identification and Location . . . . .	18

### II. TABLES

1. Standard 5-deg Cone Data Bank Summary (Tunnels A/B/C). . . . .	20
2. Model Configuration Designation. . . . .	21
3. Estimated Uncertainties . . . . .	22
4. Test Summary . . . . .	28

### III. SAMPLE TABULATED DATA

1. Sample Tabulated Data . . . . .	38
------------------------------------	----

# NOMENCLATURE

A	Reference area, 28,274 in. <sup>2</sup>
AB	Base area, 28,274 in. <sup>2</sup>
A.C.	Aerodynamic center location, body axes, inches from model nose, $XMRP-(CLM-A \cdot L/CN-A)$
A.C.P	Aerodynamic center location, missile axes, inches from model nose, $XMRP-(CLMP-A \cdot L/CNP-A)$
ALPHA	Angle of attack, deg
ALPI	Indicated sector pitch angle, deg
ALPP	Total angle of attack, missile axes, deg
BETA	Sideslip angle, deg
CA	Forebody axial-force coefficient, body axes, CAT-CAB
CAB	Base axial-force coefficient, body axes, $-AB(PBA-P)/Q \cdot A$
CAP	Forebody axial-force coefficient, missile axes
CAT	Total axial-force coefficient, body axes, total axial force/ $Q \cdot A$
CLL	Rolling-moment coefficient, body axes, rolling moment/ $Q \cdot A \cdot L$
CLLP	Rolling-moment coefficient, missile axes
CLM	Forebody pitching-moment coefficient, body axes, pitching-moment/ $Q \cdot A \cdot L$
CLM-A	Slope of CLM versus ALPHA curve, deg <sup>-1</sup>
CLMO	Value of CLM at CN = 0
CLMP	Forebody pitching-moment coefficient, missile axes
CLMPO	Value of CLMP at CNP = 0
CLMP-A	Slope of CLMP versus ALPP curve, deg <sup>-1</sup>



CLN	Yawing-moment coefficient, body axes, yawing-moment, $Q \cdot A \cdot L$
CLNO	Value of CLN at $CY = 0$
CLNP	Yawing-moment coefficient, missile axes
CLNPO	Value of CLNP at $CYP = 0$
CN	Normal-force coefficient, body axes, normal force/ $Q \cdot A$
CN-A	Slope of CN versus ALPHA curve, $\text{deg}^{-1}$
CNP	Normal-force coefficient, missile axes
CNP-A	Slope of CNP versus ALPP curve, $\text{deg}^{-1}$
CODE	Model configuration number
CONFIG	Model configuration designation
CY	Side-force coefficient, body axes, side force/ $Q \cdot A$
CYP	Side-force coefficient, missile axes
L	Reference length, 34.29 in.
LM	Model length, 34.29 in.
M	Free-stream Mach number
NCP	Normal-force center-of-pressure location, body axes, inches from model nose, $XMRP - (CLM - CLMO) \cdot L/CN$
NCPP	Normal-force center-of-pressure location, missile axes, inches from model nose, $XMRP - (CLMP - CLMPO) \cdot L/CNP$
P	Free-stream static pressure, psia
PBA	Average base pressure, psia
PBD	Fast response base pressure, psia
PB1-PB4	Base pressure, psia
PHI	Roll angle, deg
PHII	Indicated roll angle, deg
PN	Data point number
PT	Tunnel stilling chamber pressure, psia

Q	Free-stream dynamic pressure, psia
RB	Model base radius, 3.00 in.
RE	Free-stream unit Reynolds number, $\text{ft}^{-1}$
RN	Model nose radius, in.
RUN	Data set identification number
T	Free-stream static temperature, $^{\circ}\text{R}$
TDPC	Dew point temperature as measured by Cambridge Instrument, $^{\circ}\text{F}$
TDPD	Dew point temperature as measured by Dupont Instrument, $^{\circ}\text{F}$
TT	Tunnel stilling chamber temperature, $^{\circ}\text{R}$
TXL	Tunnel axial location of model nose (see Fig. 4), in.
XMRP	Distance from model moment reference point to model nose, in.
YCP	Side-force center-of-pressure location, body axes, inches from model nose, $\text{XMRP} - (\text{CLN} - \text{CLNO}) \cdot \text{L/CY}$
YCPP	Side-force center-of-pressure location, missile axes, inches from model nose, $\text{XMRP} - (\text{CLNP} - \text{CLNPO}) \cdot \text{L/CYP}$

## 1.0 INTRODUCTION

The work reported herein was conducted by the Arnold Engineering Development Center (AEDC), Air Force Systems Command (AFSC), under Program Element 65807F, Control Number 9T03-00-9. The results were obtained by ARO, Inc., AEDC Group (a Sverdrup Corporation Company), operating contractor for the AEDC, AFSC, Arnold Air Force Station, Tennessee. The test was conducted in the von Kármán Gas Dynamics Facility (VKF), Tunnel A during the period of April 30, 1979 through August 1, 1979 under ARO Project No. V41A-07.

One objective of this test was to provide data for the "high quality" data bank of the VKF standard 5-deg cone in Tunnels A, B, and C. The standard cone model (and data bank) will be used for defining test section flow nonuniformity effects and evaluating the performance of the total system (balance-support hardware, model dynamics, data acquisition systems, data reduction techniques, etc.) on a routine and systematic basis using "selected" test installations. Table 1 shows the proposed data bank with the data obtained in previous tests\* and also including the results of this test. Another objective of the test was to determine the effects on static force data of the following: tunnel-nozzle jack setting errors, tunnel-flow humidity, and tunnel-sidewall misalignment.

The test was conducted in two phases: The finless configurations were tested in Phase I, and the finned configurations in Phase II.

Static stability, axial force, and base pressure data were obtained at  $M_\infty = 1.5$  through 4.0 in Tunnel A for Reynolds numbers from  $0.6 \times 10^6/\text{ft}$  to  $3.7 \times 10^6/\text{ft}$ . The angle-of-attack and angle-of-sideslip range was  $-11$  to  $11$  deg and the roll angle ranged from  $-180$  deg to  $180$  deg. Model flow-field photographs were obtained on all configurations at selected model attitudes and test conditions.

Inquiries to obtain copies of the test data should be directed to AEDC/DOOV, Arnold Air Force Station, Tennessee 37389. A microfilm record has been retained in the VKF at AEDC.

## 2.0 APPARATUS

### 2.1 TEST FACILITY

Tunnel A (Fig. 1) is a continuous, closed-circuit, variable density wind tunnel with an automatically driven flexible-plate-type nozzle and a 40- by 40-in. test section. The tunnel can be operated at Mach numbers from 1.5 to 6 at maximum stagnation pressures from 29 to 200 psia, respectively, and stagnation temperatures up to  $750^\circ\text{R}$  at Mach number 6. Minimum operating pressures range from about one-tenth to one-twentieth of the maximum at each Mach number. The tunnel is equipped with a model injection system that allows removal of the model from the test section

\*Jenke, Leroy M. "Static Force Tests of the AEDC-VKF Standard 5-Deg Cone in Tunnels A ( $M_\infty = 3.0$  to  $5.5$ ) and B ( $M_\infty = 6$ )." AEDC-TSR-78-V20, August 1978.

while the tunnel remains in operation. A description of the tunnel and airflow calibration information may be found in the Test Facilities Handbook\*.

## 2.2 TEST ARTICLE

The standard cone model (Fig. 2) is a 5-deg, half-angle cone with a 6-in. base diameter fabricated from stainless steel. There are two basic interchangeable nose sections: sharp (0.002-in. spherical radius), and 12.5 percent blunt ( $R_N/R_B = 0.125$ ). The virtual length of the sharp cone is 34.290 inches and the model wall thickness is typically 0.25 in. Boundary layer trips (Fig. 3) were used to ensure a fully turbulent boundary layer over most of the model surface. These trips were machined on the sharp nose configurations and consisted of grit applied on the blunt nose configurations. A cylindrical section with four rectangular fins was also provided (Fig. 2). A wide range of balance adapters exist to fit the model to most VKF balances (normal load range from 80 to 1000 lbs). The model components designation is presented in Table 2. The model installations in the tunnel for Phase I and Phase II are shown in Figure 4.

## 2.3 TEST INSTRUMENTATION

The measuring devices, recording devices, and calibration methods used for all measured parameters are listed in Table 3 along with the estimated measurement uncertainties. The fast-response base pressure measurement (PBD) taken during continuous-sweep runs was made with a low-volume transducer. This transducer was used to measure the base pressure trend from a static value obtained by averaging PB1-PB4.

## 3.0 TEST DESCRIPTION

### 3.1 TEST CONDITIONS AND PROCEDURES

#### 3.1.1 General

A summary of the nominal test conditions at each Mach number is given below.

M	PT, psia	TT, °R	Q, psia	P, psia	RE x 10 <sup>-6</sup> /ft
4.0	46.9	600	3.46	0.31	3.7
3.75	41.2	600	3.75	0.38	↓
3.25	30.2	580	4.20	0.57	↓
3.0	26.4	↓	4.53	0.72	↓
3.0	11.4	↓	1.96	0.31	1.6
2.75	23.2	↓	4.89	0.93	3.7
2.5	20.3	↓	5.20	1.19	↓
2.5	8.8	↓	2.25	0.52	1.6
2.25	17.9	↓	5.49	1.55	3.7
2.0	14.6	545	5.23	1.87	↓
2.0	13.8	↓	4.94	1.76	3.5
2.0	6.3	↓	2.25	0.81	1.6
1.75	13.2	↓	5.32	2.48	3.7
1.62	12.7	↓	5.33	2.90	↓
1.5	12.3	↓	5.28	3.35	↓
1.5	5.3	↓	2.27	1.44	1.6

\*Test Facilities Handbook (Eleventh Edition). "von Kármán Gas Dynamics Facility Vol. 3" Arnold Engineering Development Center, June 1979.

At some test conditions, particularly at subatmospheric stagnation pressures, the humidity level of the tunnel flow affects the test section Mach number. The Tunnel A sidewall Mach number probe is used periodically when testing at these conditions to monitor deviations from the standard calibrated Mach numbers. When a deviation is measured, the free-stream conditions are corrected and the actual Mach number is printed on the data tabulations.

A test summary showing all configurations tested and the variables for each is presented in Table 4.

In the VKF continuous-flow wind tunnels (A, B, C), the model is mounted on a sting support mechanism in an installation tank directly underneath the tunnel test section. The tank is separated from the tunnel by a pair of fairing doors and a safety door. When closed, the fairing doors, except for a slot for the pitch sector, cover the opening to the tank and the safety door seals the tunnel from the tank area. After the model is prepared for a data run, the personnel access door to the installation tank is closed, the tank is vented to the tunnel flow, the safety and fairing doors are opened, the model is injected into the airstream, and the fairing doors are closed. After the data are obtained, the model is retracted into the tank and the sequence is reversed with the tank vented to atmosphere to allow access to the model in preparation for the next run. The sequence is repeated for each configuration change.

Model attitude positioning and data recording were accomplished with the point-pause and sweep modes of operation, using the VKF Model Attitude Control System (MACS). Model pitch and yaw requirements were entered into the controlling computer prior to the test. Model positioning and data recording operations were performed automatically during the test by selecting the list of desired model attitudes and initiating the system.

The effects on static force data of tunnel-nozzle jack setting errors, tunnel-flow humidity and tunnel-sidewall misalignment were studied as follows. Tunnel-nozzle jack setting errors were simulated by driving specific jacks off their nulled position 0.050 or 0.075 inches toward the tunnel centerline. The test summary, Table 4, denotes which jacks were driven and the amount. Figure 5 shows a view of the Tunnel A nozzle with the identification and location of the nozzle jacks. Tunnel-flow humidity effects were obtained by opening atmospheric intake valve (007) and bypassing the driers normally in the tunnel circuit. Data were obtained periodically as the dew point temperature increased. The effects of tunnel-sidewall misalignment were simulated by placing a strip of aluminum tape 0.005 inches thick on the non-operating sidewall from the top to the bottom of the tunnel. A 0.010-inch step was simulated by using two strips of tape. The location of the leading edge of the tape is shown in Fig. 4b.

### 3.1.2 Data Acquisition

Data were recorded in either the point-pause or sweep mode of operation, using the MACS. The mode for each data group is identified in the test summary (Table 4).

The point-pause data were obtained for finite values of ALPHA, PHI, and/or BETA with a delay before each data point to allow the base pressures to stabilize. Each data point for this mode of operation represents the resultant of a Kaiser-Bessel digital filter utilizing 16 samples taken over a time span of 0.0208 sec. For the retract data, a data point was automatically taken every 2 seconds as the model was retracted from the tunnel to obtain a data point approximately every inch in TXL.

The continuous-sweep data were obtained for a fixed value of PHI with a sweep (ALPHA) rate of 0.5 deg/sec or a fixed value of ALPHA with a roll (PHI) rate of 3.0 deg/sec. A data sample was recorded every 0.0208 sec, and 16 samples were applied to a Kaiser-Bessel digital filter to produce a data point every 0.156 and 0.936 deg in pitch and roll, respectively. The data were then interpolated to obtain the data at the desired model attitudes.

### 3.2 DATA REDUCTION

The cone static force data were obtained by utilizing the tunnel data acquisition system as described in Section 3.1.2. The force and moment measurements were reduced to coefficient form by using the digitally filtered data points and correcting the first- and second-order balance interaction effects. The coefficients were also corrected for model tare weight and balance-sting deflections. Model attitude, tunnel stilling chamber pressure, and fast-response base pressure were also calculated from digitally filtered values.

The aerodynamic force and moment coefficients are presented in the body and nonrolling body (missile) axis systems. For the missile axis system, the normal-force direction is always in the pitch plane of the tunnel and normal to the longitudinal axis of the model. In the body axis system, the pitching and yawing moment coefficients are referenced to two points on the model centerline which were (1/2) LM and (2/3) LM from the model nose. The missile axis data were calculated from the body axis data referenced to the (2/3) LM moment reference point. Model length (34.290 in.) and base area (28.274 in.<sup>2</sup>) were used as the reference length and area for the aerodynamic coefficients.

For selected runs, the body-axis data which were referenced to the (2/3) LM moment reference point were corrected for small tunnel-flow nonuniformities. The corrected data were then used to evaluate center of pressure locations. Those runs whose data were corrected are identified in the Test Summary, Table 4.

### 3.3 UNCERTAINTY OF MEASUREMENTS

In general, instrumentation calibrations and data uncertainty estimates were made by using methods recognized by the National Bureau of Standards (NBS).<sup>\*</sup> Measurement uncertainty is a combination of bias and precision errors defined as:

$$U = \pm(B + t_{95}S)$$

where B is the bias limit, S is the sample standard deviation, and  $t_{95}$  is the 95th percentile point for the two-tailed Student's "t" distribution, (95-percent confidence interval) which for sample sizes greater than 30 is taken equal to 2.

Estimates of the measured data uncertainties for this test are given in Table 3a. With the exception of the force and moment balance, data uncertainties are determined from in-place calibrations through the data recording system and data reduction program. Static load hangings on the balance simulate the range of loads and center-of-pressure locations anticipated during the test, and measurement errors are based on differences between applied loads and corresponding values calculated from the balance equations used in the data reduction. Load hangings to verify the balance calibration are made in-place on the assembled model.

Propagation of the bias and precision errors of measured data through the calculated data was made in accordance with the reference noted below, and the results are given in Table 3b.

### 4.0 DATA PACKAGE PRESENTATION

The data package contains tabulated model aerodynamic force and moment data presented in the body and missile axis systems. Sample tabulations of the data found in the data package are given in Appendix III.

The body axis data about the (2/3) LM moment reference point are presented twice for some runs. These data are presented both corrected and uncorrected for tunnel-flow nonuniformities. For the runs in which tunnel-flow humidity effects were being studied, these data are presented both corrected and uncorrected for the tunnel-flow humidity effects on M and PT. The corrected data for these cases are marked accordingly.

One copy of the data package was given to AEDC/D00V, Arnold AFS, Tennessee 37389. A microfilm copy was retained in the VKF at AEDC. Copies of the photographic data and installation/configuration photographs were also retained at the VKF.


---

<sup>\*</sup>Thompson, J. W. and Abernethy, R. B. et al. "Handbook Uncertainty in Gas Turbine Measurements." AEDC-TR-73-5 (AD755356), February 1973.


APPENDIX I

ILLUSTRATIONS






a. Tunnel assembly



b. Tunnel test section  
Fig. 1 Tunnel A


All Dimensions in Inches Unless Noted

12.5-percent Blunt  
Nose Section



a. Model External Geometry (Basic Cone)

Fig. 2 Model Details




b. Fin Extension

Fig. 2 Concluded

Trips are not drawn to scale.

All Dimensions in Inches  
Unless Noted




$h_{max}$	$h_{min}$	Number of Pyramids around the Circumference
0.030	0.019	33

a. Trips for sharp nose configurations, T30C

Fig. 3 Boundary Layer Trip Details

All Dimensions in Inches




b. Trip for blunt nose configuration, T06R

Fig. 3 Concluded

# 40-INCH SUPERSONIC TUNNEL A

SCALE - 1/5




a. Phase I  
Fig. 4 Installation Sketches

# 40-INCH SUPERSONIC TUNNEL A

SCALE-1/3

Leading Edge of  
Tape at STA. 60.22




PIN A

b. Phase II

Fig. 4 Concluded

All Dimensions in Inches



18

Only Top Plate Shown

Bottom Plate Jack Locations are Identical to Top

Bottom Plate Jack Identification is Top + 40 (e.g., 19 on Top, 59 on Bottom)

Fig. 5 Tunnel A Nozzle Jack Identification and Location



**APPENDIX II**

**TABLES**

TABLE I  
Standard 5-Deg Cone Data Bank Summary (Tunnels A/B/C)

Wind Tunnel		A															B		C
Config.	Re $\times 10^6$ /ft	1.50	1.75	2.00	2.25	2.50	2.75	3.00	3.25	3.50	3.75	4.00	4.50	5.00	5.50	6.00	8.00	10.00	
Sharp	0 to 1																		
	1 to 2	X		X				X		X									
	2 to 3																		
	3 to 4*	X		X	X	X		X											
	4 to 5																		
	5 to 7																		
	7 to 9																		
Blunt	0 to 1																		
	1 to 2	X		X		X		X											
	2 to 3																		
	3 to 4*	X		X	X	X		X											
	4 to 5																		
	5 to 7																		
	7 to 9																		

\* Primary Reynolds Number =  $3.7 \times 10^6$ /ft

o Planned  
x Accomplished

TABLE 2  
MODEL CONFIGURATION DESIGNATION

Nose Designation (NXX.X)

N00.0	sharp nose
N12.5	spherically blunted nose( $RN/RB = 0.125$ )

Boundary-Layer Trip Designation (TXXX)

T30C	machined trips, $h_{\max} = 0.030$ in.
T06R	grit trips, $h_{\max} = 0.006$ in.

Fin Designation (FX)

F0	no fins or body extension
F2	two fins (horizontal plane)
F4	four fins

Base Plate Designation (BX)

B0	no base plate
----	---------------

TABLE 3. ESTIMATED UNCERTAINTIES  
a. Basic Measurements

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT <sup>a</sup>							Range	Type of Measuring Device	Type of Recording Device	Method of System Calibration
	Precision Index (S)		Bias (B)		Uncertainty $\pm(B + t_{95}S)$						
	Percent Reading	Unit of Measure	Degree of Freedom	Percent Reading	Unit of Measure	Percent Reading	Unit of Measure				
PT, psia	$\pm 0.002$ $\pm 0.002$ $\pm 0.007$	$\pm 0.011$	$>30$ $>30$ $>30$	$\pm 0.2$ $\pm 0.2$	$\pm 0.015$ $\pm(0.2\%+0.004)$ $\pm(0.2\%+0.014)$	$\pm 0.015$	0 to 5.3 5.5 to 15 15 to 60	Bell and Howell Variable Capacitance Transducer	Digital Data Acquisition System Analog to Digital Converter	In Place Air Dead Weight Calibration	
TT, °F	$\pm 1.5$	0*	$>30$		$\pm 3$		0 to 300	Copper-Constantan Thermocouple	Logic Temperature Instrument/Digital Multiplexer	Thermocouple Verification of NBS Conformity/Voltage Substitution Calibration	
ALPI, deg	$\pm 0.025$	0*	$>30$		$\pm 0.05$		$\pm 15$	Potentiometer	Digital Data Acquisition System Analog to Digital Converter	Precision Inclination Gage Reading	
PHI, deg	$\pm 0.075$	0*	$>30$		$\pm 0.15$		$\pm 180$	Six-Component Strain Gage Balance 4.01-Y-36-043		Static Loading	
Norcal Force, lb	$\pm 0.253$	$\pm 0.082$	$>30$		$\pm 0.588$		$\pm 500$				
Pitching Moment, in.-lb	$\pm 1.350$	$\pm 0.519$	$>30$		$\pm 3.219$		$\pm 1850$				
Side Force, lb	$\pm 0.368$	$\pm 0.110$	$>30$		$\pm 0.846$		$\pm 250$				
Yawing Moment, in.-lb	$\pm 1.826$	$\pm 0.477$	$>30$		$\pm 4.129$		$\pm 925$				
Rolling Moment, in.-lb	$\pm 0.082$	$\pm 0.012$	$>30$		$\pm 0.136$		$\pm 100$				
Axial Force, lb	$\pm 0.151$	$\pm 0.007$	$>30$		$\pm 0.309$		0 to 300	Druck(Variable Resistance)Transducer		In Place Air Dead Weight Calibration	
Fast Response Base Pressure, psia	20.01	0*	$>30$		$\pm 0.08$		$\pm 15$				
P81-P84, psia	20.175	$\pm 0.0015$	$>30$ $>30$		$\pm 0.15$		0 to 2 2 to 15	Bell and Howell Variable Capacitance Transducer			
Longitudinal Moment Transfer Distance, in	$\pm 0.0025$	0*	$>30$		$\pm 0.003$		$\pm 0.003$	Precision Height Gage and Micro-meters		Calibrated in the Standards Laboratory	

<sup>a</sup> Thompson, J. W. and Abernethy, R. B. et al. "Handbook Uncertainty in Gas Turbine Measurements," AEC-TR-73-8 (AD 785356), February 1973.

\* Assumed to be zero.

VR-16 (8/79)

**TABLE 3. Continued**

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT*								Type of Measuring Device	Type of Recording Device	Method of System Calibration	
	Precision Index (\$)			Bias (\$)			Uncertainty $\pm(B + 19S)$					
	Percent of Reading	Unit of Measure	Degree of Freedom	Percent of Reading	Unit of Measure	Percent of Reading	Unit of Measure					
CM		0.0047					0.0013			4.0/3.7		
		0.0051					0.0013			3.75/3.7		
		0.0062					0.0017			3.25/3.7		
		0.0059					0.0018			3.0/3.7		
		0.0037					0.0012			3.0/1.6		
		0.0022					0.0012			2.75/3.7		
		0.0042					0.0012			2.5/3.7		
		0.0029					0.0011			2.5/1.6		
		0.0031					0.0011			2.25/3.7		
		0.0027					0.0018			2.0/3.7		
		0.0045					0.0016			2.0/3.5		
		0.0021					0.0011			2.0/1.6		
		0.0020					0.0008			1.75/3.7		
		0.0018					0.0011			1.62/3.7		
		0.0040					0.0016			1.5/3.7		
	CLM		0.0004					0.0002			4.0/3.7	
		0.0004					0.0002			3.75/3.7		
		0.0010					0.0003			3.25/3.7		
		0.0008					0.0003			3.0/3.7		
		0.0003					0.0001			3.0/1.6		
		0.0003					0.0001			2.75/3.7		
		0.0007					0.0002			2.5/3.7		
		0.0003					0.0001			2.5/1.6		
		0.0003					0.0001			2.25/3.7		
		0.0008					0.0004			2.0/3.7		
		0.0007					0.0003			2.0/3.5		
		0.0003					0.0001			2.0/1.6		
		0.0002					0.0001			1.75/3.7		
		0.0003					0.0001			1.62/3.7		
		0.0007					0.0002			1.5/3.7		
		0.0007					0.0016			1.5/1.6		
CT		0.0036					0.0011			4.0/3.7		
		0.0035					0.0010			3.75/3.7		
		0.0021					0.0009			3.25/3.7		
		0.0029					0.0009			3.0/3.7		
		0.0067					0.0020			3.0/1.6		
		0.0027					0.0008			2.75/3.7		
		0.0034					0.0013			2.5/3.7		
		0.0036					0.0017			2.5/1.6		

Thompson, J. V. and Abernethy, E. B. et al. "Handbook Uncertainty in Gas Turbine Measurements." AEDC-TN-73-5 (AD 755366), February 1973.

77-10 (2/79)

TABLE 3. Continued

b. Calculated Parameters

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT <sup>a</sup>							M/REL <sup>10-6</sup>	Type of Measuring Device	Type of Recording Device	Method of System Calibration
	Precision Index (S)		Bias (B)		Uncertainty $\pm(B + 1.95S)$						
	Percent of Reading	Unit of Measurement	Degree of Freedom	Percent of Reading	Unit of Measurement	Percent of Reading	Unit of Measurement				
CT		0.0024				0.0007		0.0055	2.25/3.7		
		0.0033				0.0012		0.0078	2.0/3.7		
		0.0026				0.0008		0.0060	2.0/3.5		
		0.0038				0.0017		0.0133	2.0/1.6		
		0.0023				0.0007		0.0057	1.75/3.7		
		0.0024				0.0007		0.0055	1.62/3.7		
CL		0.0025				0.0007		0.0057	1.5/3.7		
		0.0037				0.0017		0.0134	1.5/1.6		
		0.0006				0.0002		0.0014	4.0/3.7		
		0.0005				0.0002		0.0012	3.75/3.7		
		0.0005				0.0001		0.0011	3.25/3.7		
		0.0010				0.0001		0.0011	3.0/3.7		
		0.0004				0.0003		0.0023	3.0/1.6		
		0.0004				0.0001		0.0009	2.75/3.7		
		0.0009				0.0001		0.0020	2.5/3.7		
		0.0004				0.0002		0.0009	2.25/3.7		
		0.0004				0.0001		0.0009	2.0/3.7		
		0.0004				0.0001		0.0009	2.0/3.5		
		0.0009				0.0002		0.0020	2.0/1.6		
		0.0004				0.0001		0.0009	1.75/3.7		
CL		0.0004				0.0001		0.0009	1.62/3.7		
		0.0009				0.0001		0.0009	1.5/3.7		
		0.0004				0.0001		0.0009	1.5/3.7		
		0.0009				0.0002		0.0020	1.5/1.6		
		0.0002				0.0004		0.0008	4.0/3.7		
		0.0002				0.0000		0.0004	3.75/3.7		
		0.0002				0.0000		0.0004	3.25/3.7		
		0.0003				0.0000		0.0006	3.0/3.7		
		0.0003				0.0001		0.0007	3.0/1.6		
		0.0001				0.0000		0.0002	2.75/3.7		
		0.0001				0.0000		0.0002	2.5/3.7		
		0.0003				0.0000		0.0006	2.25/3.7		
		0.0001				0.0000		0.0002	2.0/3.7		
		0.0004				0.0000		0.0008	2.0/3.5		
		0.0006				0.0000		0.0012	2.0/1.6		
		0.0004				0.0001		0.0009	1.75/3.7		
	0.0004				0.0000		0.0008	1.62/3.7			
	0.0004				0.0000		0.0006	1.5/3.7			
	0.0003				0.0000		0.0006	1.5/3.7			
	0.0004				0.0001		0.0009	1.5/1.6			

<sup>a</sup> Thompson, J. W. and Abernethy, R. B. et al. "Handbook Uncertainty in Gas Turbine Measurements." AMDC-TB-73-9 (AD 755356), February 1973.

TABLE 3. Continued  
b. Calculated Parameters

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT*						M/RX10 <sup>-6</sup>	Type of Measuring Device	Type of Recording Device	Method of System Calibration	
	Precision Index (\$)		Degree of Freedom	Bias (B)		Uncertainty ±(B + t95)					
	Percent of Reading	Unit of Measurement		Percent Reading	Unit of Measurement	Percent Reading					Unit of Measurement
C17		0.0019		0.0003		0.0003	0.0041	4.0/3.7			
		0.0020		0.0003		0.0003	0.0043	3.75/3.7			
		0.0023		0.0004		0.0004	0.0050	3.25/3.7			
		0.0020		0.0005		0.0005	0.0045	3.0/3.7			
		0.0031		0.0004		0.0004	0.0066	3.0/1.6			
		0.0017		0.0004		0.0004	0.0038	2.75/3.7			
		0.0015		0.0005		0.0005	0.0035	2.5/3.7			
		0.0026		0.0003		0.0003	0.0037	2.5/1.6			
		0.0016		0.0008		0.0008	0.0038	2.25/3.7			
		0.0016		0.0007		0.0007	0.0045	2.0/3.7			
		0.0027		0.0006		0.0006	0.0060	2.0/1.6			
		0.0014		0.0006		0.0006	0.0034	1.75/3.7			
		0.0013		0.0004		0.0004	0.0030	1.62/3.7			
		0.0011		0.0007		0.0007	0.0029	1.5/3.7			
		0.0024		0.0007		0.0007	0.0055	1.5/1.6			
C1		0.0023		0.0003		0.0003	0.0019	4.0/3.7			
		0.0025		0.0003		0.0003	0.0053	3.75/3.7			
		0.0035		0.0004		0.0004	0.0064	3.25/3.7			
		0.0031		0.0005		0.0005	0.0067	3.0/3.7			
		0.0038		0.0005		0.0005	0.0081	3.0/1.6			
		0.0029		0.0005		0.0005	0.0053	2.75/3.7			
		0.0027		0.0006		0.0006	0.0060	2.5/3.7			
		0.0035		0.0006		0.0006	0.0076	2.5/1.6			
		0.0038		0.0007		0.0007	0.0083	2.25/3.7			
		0.0049		0.0009		0.0107	2.0/3.7				
		0.0052		0.0010		0.0112	2.0/3.5				
		0.0054		0.0009		0.0117	2.0/1.6				
		0.0057		0.0011		0.0125	1.75/3.7				
		0.0075		0.0007		0.0157	1.62/3.7				
		0.0117		0.0014		0.0248	1.5/3.7				
	0.0119		0.0015		0.0253	1.5/1.6					
M		0.009		0.008		0.018	4.0/3.7				
		0.010		0.010		0.020	3.75/3.7				
		0.013		0.013		0.026	3.25/3.7				
		0.0085		0.0085		0.017	3.0/3.7				
		0.0085		0.0085		0.017	3.0/1.6				
		0.009		0.009		0.016	2.75/3.7				
		0.006		0.006		0.012	2.5/3.7				
	0.006		0.006		0.006	2.5/1.6					

\* Thompson, J. V. and Abernathy, R. B. et al. "Handbook Uncertainty in Gas Turbine Measurements." AEC-TR-73-5 (AD 745394), February 1973.

\*Assumed to be zero  
79-16 (2/73)

TABLE 3. Continued  
b. Calculated Parameters

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT <sup>a</sup>										Type of Measuring Device	Type of Recording Device	Method of System Calibration
	Precision Index (S)		Bias (B)		Uncertainty $\pm(B + 1.95S)$								
	Percent of Reading	Unit of Measurement	Degree of Freedom	Percent of Reading	Unit of Measurement	Percent of Reading	Unit of Measurement		Percent of Reading	Unit of Measurement			
							Percent of Reading	Unit of Measurement					
H	0.0075				0 <sup>+</sup>			0.015			2.35/3.7		
	0.008				0 <sup>+</sup>			0.016			2.0/2.7		
	0.008				0 <sup>+</sup>			0.016			2.0/2.5		
	0.008				0 <sup>+</sup>			0.016			2.0/1.5		
	0.0075				0 <sup>+</sup>			0.015			1.5/1.6		
	0.009				0 <sup>+</sup>			0.018			1.5/3.7		
	0.0125				0 <sup>+</sup>			0.025			1.5/3.7		
	0.0125				0 <sup>+</sup>			0.025			1.5/1.6		
	0.0037				0.0006			0.0080			4.0/3.7		
	0.0032				0.0006			0.0112			3.75/3.7		
P, psia	0.0108				0.0011			0.0227			3.25/3.7		
	0.0092				0.0014			0.0386			3.0/3.7		
	0.0040				0.0006			0.0386			2.0/1.6		
	0.0113				0.0018			0.0244			2.0/3.7		
	0.0024				0.0011			0.0246			2.5/3.7		
	0.0048				0.0011			0.0107			2.5/1.6		
	0.0182				0.0031			0.0395			2.25/3.7		
	0.0232				0.0037			0.0501			2.0/3.7		
	0.0219				0.0036			0.0474			2.0/3.5		
	0.0100				0.0017			0.0217			2.0/1.6		
Q, psia	0.0283				0.0049			0.0615			1.75/3.7		
	0.0389				0.0034			0.0812			1.62/3.7		
	0.0607				0.0068			0.1282			1.5/3.7		
	0.0261				0.0030			0.0552			1.5/1.6		
	0.0260				0.0069			0.0589			4.0/3.7		
	0.0316				0.0075			0.0707			3.75/3.7		
	0.0462				0.0083			0.1007			3.25/3.7		
	0.0321				0.0091			0.0733			3.0/3.7		
	0.0139				0.0039			0.0317			3.0/1.6		
	0.0215				0.0097			0.0727			2.75/3.7		

<sup>a</sup> Thompson, J. W. and Abernethy, R. B. et al. "Handbook Uncertainty in Gas Turbine Measurements." AEDC-TN-73-3 (AD 755396), February 1973.

<sup>b</sup>Assumed to be zero

72-16 (2/79)



TABLE 3. Concluded  
b. Calculated Parameters

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT*							M/REX-10 <sup>-6</sup>	Type of Measuring Device	Type of Recording Device	Method of System Calibration
	Precision Index (\$)		Bias (B)		Uncertainty ±(B + 19S)						
	Percent of Reading	Unit of Measure	Degree of Freedom	Percent of Reading	Unit of Measure	Percent of Reading	Unit of Measure				
REX-10 <sup>-6</sup> , ft <sup>-1</sup>	0.0220				0.0074		0.0514	4.0/3.7			
	0.0237				0.0074		0.0548	3.75/3.7			
	0.0292				0.0074		0.0658	3.25/3.7			
	0.0218				0.0074		0.0510	3.0/3.7			
	0.0094				0.0033		0.0221	3.0/1.6			
	0.0210				0.0074		0.0494	2.75/3.7			
	0.0179				0.0074		0.0433	2.5/3.7			
	0.0078				0.0033		0.0149	2.5/1.6			
	0.0192				0.0074		0.0458	2.25/3.7			
	0.0181				0.0071		0.0433	2.0/3.7			
	0.0043				0.0033		0.0196	2.0/1.6			
	0.0170				0.0073		0.0413	1.75/3.7			
	0.0172				0.0068		0.0344	1.62/3.7			
	0.0074				0.0033		0.0161	1.5/3.7			
	ALPHA	0.05				0+		0.10	All		
BETA	0.05				0+		0.10	All			
PRD, pole	0.0015				0+		0.0030	4.0/3.7			
	0.0015				0+		0.0030	3.75/3.7			
	0.0015				0+		0.0030	3.25/3.7			
	0.0015				0+		0.0030	3.0/3.7			
	0.0015				0+		0.0030	3.0/1.6			
	0.0015				0+		0.0030	2.75/3.7			
	0.0015				0+		0.0030	2.5/3.7			
	0.0015				0+		0.0030	2.5/1.6			
	0.0015				0+		0.0030	2.25/3.7			
	0.0015				0+		0.0030	2.0/3.7			
	0.0015				0+		0.0030	2.0/3.5			
	0.0015				0+		0.0030	2.0/1.6			
	0.0016				0+		0.0032	1.75/3.7			
	0.0017				0+		0.0034	1.62/3.7			
	0.0019				0+		0.0038	1.5/3.7			
0.0016				0+		0.0032	1.5/1.6				

Thompson, J. W. and Abernethy, R. B. et al. "Handbook Uncertainty in Gas Turbine Measurements." AEDC-TN-73-3 (AD 753560), February 1973.  
 \*Assumed to be zero.

VB-16 (8/79)

Table 4. Test Summary

M	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE $\times 10^{-6}$	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO BO	N12.5 T06R FO BO	N00.0 T30C F4 BO	
4.0	ALPHA	O	O*	47	18.0	3.7		500		
			V*					501		
			V+					502		
			V-					503		
		180	V-					504		
3.75	ALPHA	O	O*					505		
			V+					506		
			V-					x507		
		180	V-					x508		
	PHI	V-	O					x509		
3.25	ALPHA	O	O*					510		
			V+					511		
			V-					x512		
		180	V-					x513		
	PHI	V-	O					x514		
3.0	ALPHA	O	O*				690	515	811	
			V*					516		
			V+				691 699	517	812	
			V-				692 700	518	x813	
		180	V-				693 701	519	x814	
		O	O*				A590			TDP ~ +24°
			V+				A591			
			V-				A592			
	TXL	O	O	V*			694		818	
	PHI	V-	O	47					x815	
		V+	5						816	
		V-	-5						817	
	PHI	V-	O						x835	after hand nulling nozzle
	TXL	O	O	V*					836	
	PHI	V-	O	47					x837	after RMAC nulling nozzle
	TXL	O	O	V*					838	

\* Point Pause

- Continuous Sweep (-) to (+)

+ Continuous Sweep (+) to (-)

x Runs presented corrected and uncorrected for nonuniformities

A Runs presented corrected and uncorrected for humidity

Table 4. Continued

M	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE <sup>-</sup> x 10 <sup>-6</sup>	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO BO	N12.5 T06R FO BO	N00.0 T80C F4 BO	
3.0	PHI	V <sup>-</sup>	0	47	18.0	3.7			*839	no nulling of nozzle
	TXL	0	0	V*					840	↓
	PHI	V <sup>-</sup>	0	47					*841	after RMAC nulling nozzle
	TXL	0	0	V*					842	↓
	ALPHA	0	0*	47					827	Jack 35 at Δ = +.050"
		↓	V <sup>+</sup>						828	
		↓	V <sup>-</sup>						829	
	↓	180	V <sup>-</sup>	↓					830	
	TXL	0	0	V*					834	
	PHI	V <sup>-</sup>	0	47					831	
		V <sup>+</sup>	5						832	
	↓	V <sup>-</sup>	-5						833	↓
	ALPHA	0	0*						819	Jack 27 at Δ = +.050"
		↓	V <sup>+</sup>						820	
		↓	V <sup>-</sup>						821	
	↓	180	V <sup>-</sup>	↓					822	
	TXL	0	0	V*					826	
	PHI	V <sup>-</sup>	0	47					823	
		V <sup>+</sup>	5						824	
	↓	V <sup>-</sup>	-5			↓			825	↓
	ALPHA	0	0*			1.6		520		
		↓	V <sup>+</sup>					521		
		↓	V <sup>-</sup>					522		
↓		180	V <sup>-</sup>			↓		523		
2.75		0	0*			3.7	685			
		↓	V <sup>+</sup>				686			
		↓	V <sup>-</sup>				687			
↓	↓	180	V <sup>-</sup>	↓	↓	↓	688			

\* Point Pause  
- Continuous Sweep (-) to (+)  
+ Continuous Sweep (+) to (-)

x Runs presented corrected and uncorrected for nonuniformities  
Δ Runs presented corrected and uncorrected for humidity

Table 4. Continued

M	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE <sup>*</sup> x 10 <sup>-6</sup>	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO 80	N12.5 T06R FO 80	N00.0 T30C F4 80	
2.75	TXL	0	0	V*	18.0	3.7	689			
2.5	ALPHA	0	0*	47			672	528		
			V*				673			
			V+				674	529		
		↓	V-				*675	530		
		180	V-				*676	531		
		-90	V-				*677			
		90	V-				*678			
	↓	0	V-				679			
	PHI	V-	0				*680			
	↓	V-	10		↓		*681			
	ALPHA	0	V-		0.8		682			
	↓	180	V-	↓	↓		683			
	TXL	0	0	V*	18.0		684			
	ALPHA		V+	42				532		
		↓	V-					533		
		180	V-	↓		↓		534		
		0	0*	47		1.6		524		
			V+					525		
		↓	V-					526		
↓		180	V-			↓		527		
2.25		0	0*			3.7	668	535		
		↓	V+				669	536		
		↓	V-				670	537		
	↓	180	V-	↓				538		
↓	TXL	0	0	V*			671			
2.0	ALPHA	0	0*	47			568	539		
↓	↓	↓	V*	↓	↓	↓		540		

\* Point Pause

- Continuous Sweep (-) to (+)

+ Continuous Sweep (+) to (-)

x Runs presented corrected and uncorrected for nonuniformities

Δ Runs presented corrected and uncorrected for humidity

Table 4. Continued

M	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE $\times 10^{-6}$	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO BO	N12.5 T06R FO BO	N00.0 T30C F4 BO	
2.0	ALPHA	0	V+	47	18.0	3.7	569	541		
	↓	↓	V-	↓			<sup>x</sup> 608	542		
	↓	180	V-	↓			571	543		
	TXL	0	0	V*			613	544		
	ALPHA	-90	V-	47			<sup>x</sup> 609			
	PHI	V-	0				<sup>x</sup> 610			
	↓	V+	10		↓		<sup>x</sup> 611			
	ALPHA	0	V-		0.8	↓	612			
		0	0*		18.0	1.6	635	549		
		↓	V+				636	550		
	↓	↓	V-				637	551		
	↓	180	V-	↓			638	552		
	TXL	0	0	V*			640			
	ALPHA	0	0*	47			<sup>A</sup> 587			TDP ~ +24°
		↓	V+				<sup>A</sup> 588			↓
		↓	V-			↓	<sup>A</sup> 589			
		0	0*			3.7	<sup>A</sup> 572	<sup>A</sup> 762		TDP ~ -6°
		↓	V+				<sup>A</sup> 573	<sup>A</sup> 763		
	↓	↓	V-				<sup>A</sup> 574			
	PHI	V-	0	↓				<sup>A</sup> 764		
	TXL	0	0	V*				<sup>A</sup> 765		↓
	ALPHA	0	V+	47				<sup>A</sup> 766		TDP ~ 0°
	PHI	V-	0	↓				<sup>A</sup> 767		↓
	TXL	0	0	V*				<sup>A</sup> 768		
↓	ALPHA	0	0*	47	↓	↓	<sup>A</sup> 575			TDP ~ +3°

\* Point Pause  
- Continuous Sweep (-) to (+)  
+ Continuous Sweep (+) to (-)

x Runs presented corrected and uncorrected for nonuniformities  
Δ Runs presented corrected and uncorrected for humidity

Table 4. Continued

A1	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE $\times 10^{-6}$	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO BO	N12.5 T06R FO BO	N00.0 T30C F4 BO	
2.0	ALPHA	0	V <sup>+</sup>	47	18.0	3.7	<sup>A</sup> 576		<sup>A</sup> 769	TDP ~ +3°
	↓	↓	V <sup>-</sup>	↓			<sup>A</sup> 577			↓
	PHI	V <sup>-</sup>	0	↓					<sup>A</sup> 770	↓
	TXL	0	0	V*					<sup>A</sup> 771	↓
	ALPHA	0	0*	47			<sup>A</sup> 578			TDP ~ +10°
			V <sup>+</sup>				<sup>A</sup> 579			↓
			V <sup>-</sup>				<sup>A</sup> 580			↓
			0*				<sup>A</sup> 581			TDP ~ +16°
			V <sup>+</sup>				<sup>A</sup> 582		<sup>A</sup> 772	↓
	↓	↓	V <sup>-</sup>	↓			<sup>A</sup> 583			↓
	PHI	V <sup>-</sup>	0	↓					<sup>A</sup> 773	↓
	TXL	0	0	V*					<sup>A</sup> 774	↓
	ALPHA	0	0*	47			<sup>A</sup> 584			TDP ~ +24°
			V <sup>+</sup>				<sup>A</sup> 585		<sup>A</sup> 775	↓
			V <sup>-</sup>			↓	<sup>A</sup> 586			↓
			0*			3.5			746	
			V <sup>+</sup>						747	
		↓	V <sup>-</sup>				616		<sup>A</sup> 748 776	
	↓	180	V <sup>-</sup>				617		<sup>A</sup> 749 793	
	PHI	V <sup>-</sup>	0				614		<sup>A</sup> 744, 777 750, 807	<sup>A</sup> 808
		V <sup>+</sup>	10				615			
		V <sup>+</sup>	5						751	
	↓	V <sup>-</sup>	-5	↓					752	
	TXL	0	0	V*			626, 633 629		753, 809 778, 810	
	ALPHA	0	V <sup>-</sup>	42			620		<sup>A</sup> 754	
	↓	180	V <sup>-</sup>				621			
	PHI	V <sup>-</sup>	0				618		<sup>A</sup> 755	
		V <sup>+</sup>	10				619			
		V <sup>+</sup>	5						756	
↓	↓	V <sup>-</sup>	-5	↓	↓	↓			757	

\* Point Pause  
- Continuous Sweep (-) to (+)  
+ Continuous Sweep (+) to (-)

x Runs presented corrected and uncorrected for nonuniformities  
Δ Runs presented corrected and uncorrected for humidity

Table 4. Continued

M	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE $\times 10^{-6}$	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO BO	N12.5 T06R FO BO	N00.0 T30C F4 BO	
2.0	ALPHA	0	V <sup>-</sup>	38	18.0	3.5			*758	
	PHI	V <sup>-</sup>	0						*759	
		V <sup>+</sup>	5						760	
	↓	V <sup>-</sup>	-5	↓					761	
	ALPHA	0	V <sup>-</sup>	37			*624			
	↓	180	V <sup>-</sup>				*625			
	PHI	V <sup>-</sup>	0				*622			
	↓	V <sup>+</sup>	10	↓			*623			
	ALPHA	0	V <sup>-</sup>	47			628			Jack 31 at $\Delta = +.050''$
	TXL	0	0	V*			627	545		↓
	TXL	0	0	47			632			Jack 31 at $\Delta = +.075''$
	ALPHA	0	0*						779	Jack 36 at $\Delta = +.050''$
		V <sup>+</sup>							780	
		V <sup>-</sup>					631		781	
	↓	180	V <sup>-</sup>						782	
	PHI	V <sup>-</sup>	0						783	
		V <sup>+</sup>	5						784	
	↓	V <sup>-</sup>	-5	↓					785	
	TXL	0	0	V*			630	546	786	↓
	TXL	0	0	47			634			Jack 36 at $\Delta = +.075''$
	ALPHA	0	V <sup>-</sup>	42					787	Jack 36 at $\Delta = +.050''$
	PHI	V <sup>-</sup>	0						788	
		V <sup>+</sup>	5						789	
	↓	V <sup>-</sup>	-5	↓					790	↓
	ALPHA	0	0*	47					795	Jack 38 at $\Delta = +.050''$
		V <sup>+</sup>							796	
		V <sup>-</sup>							797	
	↓	180	V <sup>-</sup>						798	
	PHI	V <sup>-</sup>	0						799	
		V <sup>+</sup>	5						800	
↓	↓	V <sup>-</sup>	-5	↓	↓	↓			801	↓

\* Point Pause

- Continuous Sweep (-) to (+)

+ Continuous Sweep (+) to (-)

\* Runs presented corrected and uncorrected for nonuniformities

Δ Runs presented corrected and uncorrected for humidity

Table 4. Continued

M	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE x10 <sup>-6</sup>	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO BO	N12.5 T06R FO BO	N00.0 T30C F4 BO	
2.0	TXL	0	0	V*	18.0	3.5			802	Jack 38 at $\Delta = +.050''$
	ALPHA	0	V-	38					803	
	PHI	V-	0						804	
		V+	5						805	
	↓	V-	-5	↓					806	↓
	ALPHA	0	0*	47					702	TAPE = .005''
			V+						703	
			V*						704	
			V-						705	
	↓	180	V-						706	
	PHI	V-	0						707	
		V+	5						711	
		V+	10						708	
	↓	V-	-10	↓					709	
	TXL	0	0	V*					710	↓
		0	0						728	TAPE = .010'', F2 not F4
	↓	90	0	↓					729	↓
	ALPHA	0	0*	47					730	
			V+						731	
			V-						732	
	↓	180	V-						733	
	PHI	V-	0						734	
		V+	5						735	
	↓	V-	-5	↓					736	
	TXL	0	0	V*					737	
	ALPHA	0	V-	42					738	
	PHI	V-	0						739	
		V+	5						740	
↓	↓	V-	-5	↓	↓	↓			741	↓

\* Point Pause

- Continuous Sweep (-) to (+)

+ Continuous Sweep (+) to (-)

x Runs presented corrected and uncorrected for nonuniformities

Δ Runs presented corrected and uncorrected for humidity



Table 4. Continued

M	DATA TYPE POLAR	PHI	ALPHA	TXL	C.R.	RE $\times 10^{-6}$	RUN NUMBERS FOR EACH CONFIG			REMARKS
							N00.0 T30C FO BO	N12.5 T06R FO BO	N00.0 T30C F4 BO	
2.0	ALPHA	0	V <sup>-</sup>	38	18.0	3.5			742	TAPE = .010"
	PHI	V <sup>-</sup>	0						743	
		V <sup>+</sup>	5						744	
↓	↓	V <sup>-</sup>	-5	↓		↓			745	↓
1.75	ALPHA	0	0*	47		3.7	664	555		
		↓	V <sup>+</sup>				665	556		
		↓	V <sup>-</sup>				666	557		
	↓	180	V <sup>-</sup>	↓				558		
↓	TXL	0	0	V*			667			
1.62	ALPHA	0	0*	47			660			
	↓	↓	V <sup>+</sup>	↓			661			
	↓	↓	V <sup>-</sup>	↓			662			
↓	TXL	0	0	V*			663			
1.5	ALPHA	0	0*	47			647	559		
		↓	V*				648			
		↓	V <sup>+</sup>				649	560		
		↓	V <sup>-</sup>				*650	561		
		180	V <sup>-</sup>				*651	562		
		-90	V <sup>-</sup>				*652			
		+90	V <sup>-</sup>				*653			
	↓	0	V <sup>-</sup>				654			
	PHI	V <sup>-</sup>	0				*655			
	↓	V <sup>+</sup>	10		↓		*656			
	ALPHA	0	V <sup>-</sup>		0.8		657			
	↓	180	V <sup>-</sup>	↓	0.8		658			
	TXL	0	0	V*	18.0		659			
	ALPHA	0	0*	47	↓		*593			TDP ~ +24°
↓	↓	0	V <sup>+</sup>	47	↓	↓	*594			↓

\* Point Pause

- Continuous Sweep (-) to (+)

+ Continuous Sweep (+) to (-)

x Runs presented corrected and uncorrected for nonuniformities

Δ Runs presented corrected and uncorrected for humidity

9

* Point Pause	x Runs presented corrected and uncorrected for nonuniformities
- Continuous Sweep (-) to (+)	
+ Continuous Sweep (+) to (-)	Δ Runs presented corrected and uncorrected for humidity

APPENDIX III

SAMPLE TABULATED DATA

DATE COMPUTED 31-AUG-79  
 TIME COMPUTED 11:04:53  
 DATE RECORDED 30-APR-79  
 TIME RECORDED 20:25:31  
 PROJECT NUMBER 741A-07

ARO, INC. - AEC DIVISION  
 A SYRUP CORPORATION COMPANY  
 VON HANAU GAS DYNAMICS FACILITY  
 ARMOLO AIR FORCE STATION, TENNESSEE  
 STANDARD FORCE CONE (3 DEG)  
 PAGE 1

RUN CODE M PT TT Q P T RE A REF LENGTHS(CLM,CLM,CLM)  
 502 4 4.02 46.98 599.7 3.408 0.301 141.7 0.367E+07 20.274 34.290 34.290 34.290

CONFIG  
 012.5-Y06R-70-80

BODY AXIS-XMRP = (2/3) LM

PH ALPHA	BETA	PMT	CM	CLM	CY	CLW	CLL	CLT	CAB	CA	MCP/LM	YCP/LM	A.C.	TIL
1	11.40	0.01	0.5261	-0.0081	-0.0038	0.0003	0.0000	0.1578	0.0794	0.0685	0.0821	0.6956	0.6817	46.6385
2	11.00	0.00	0.4843	-0.0075	-0.0037	0.0003	0.0000	0.1557	0.0784	0.0664	0.0822	0.7033	0.6819	46.6364
3	10.00	0.00	0.4256	-0.0066	-0.0033	0.0003	0.0000	0.1431	0.0781	0.0640	0.0823	0.6997	0.6823	46.6358
4	9.00	0.00	0.3657	-0.0058	-0.0028	0.0003	0.0000	0.1410	0.0785	0.0625	0.0824	0.7020	0.6826	46.6344
5	8.00	0.00	0.3122	-0.0048	-0.0024	0.0003	0.0000	0.1394	0.0781	0.0613	0.0825	0.7068	0.6823	46.6385
6	7.00	0.00	0.2629	-0.0040	-0.0020	0.0003	0.0000	0.1387	0.0777	0.0604	0.0820	0.6989	0.6815	46.6354
7	6.00	0.00	0.2160	-0.0033	-0.0020	0.0003	0.0000	0.1378	0.0774	0.0604	0.0822	0.7038	0.6810	46.6354
8	5.00	0.00	0.1751	-0.0027	-0.0018	0.0003	0.0000	0.1367	0.0765	0.0602	0.0826	0.7289	0.6807	46.6330
9	4.00	0.00	0.1365	-0.0022	-0.0016	0.0003	0.0000	0.1352	0.0756	0.0596	0.0833	0.7293	0.6810	46.6331
10	3.00	0.00	0.1004	-0.0017	-0.0015	0.0003	0.0000	0.1336	0.0748	0.0589	0.0839	0.7309	0.6815	46.6320
11	2.00	0.00	0.0659	-0.0011	-0.0010	0.0002	0.0000	0.1321	0.0740	0.0581	0.0848	0.7337	0.6829	46.6325
12	1.50	0.00	0.0496	-0.0009	-0.0013	0.0002	0.0000	0.1316	0.0735	0.0583	0.0860	0.7177	0.6843	46.6355
13	1.00	0.00	0.0336	-0.0006	-0.0010	0.0002	0.0000	0.1316	0.0733	0.0583	0.0857	0.7144	0.6855	46.6324
14	0.75	0.00	0.0261	-0.0004	-0.0011	0.0002	0.0000	0.1314	0.0731	0.0583	0.0857	0.7138	0.6849	46.6315
15	0.50	0.00	0.0176	-0.0003	-0.0012	0.0002	0.0000	0.1314	0.0731	0.0584	0.0864	0.7006	0.6855	46.6316
16	0.25	0.00	0.0091	-0.0002	-0.0013	0.0002	0.0000	0.1315	0.0731	0.0584	0.0887	0.7157	0.6857	46.6332
17	0.00	0.00	0.0020	-0.0000	-0.0010	0.0002	0.0000	0.1316	0.0732	0.0584	0.0817	0.7146	0.6862	46.6326
18	-0.25	0.00	0.0053	0.0001	-0.0009	0.0002	0.0000	0.1315	0.0734	0.0582	0.0842	0.7179	0.6876	46.6318
19	-0.50	0.00	0.0125	0.0003	-0.0009	0.0002	0.0000	0.1315	0.0734	0.0580	0.0856	0.7171	0.6879	46.6337
20	-0.75	0.00	0.0213	0.0005	-0.0008	0.0002	0.0000	0.1316	0.0734	0.0582	0.0879	0.7115	0.6872	46.6335
21	-1.00	0.00	0.0299	0.0007	-0.0010	0.0002	0.0000	0.1318	0.0732	0.0582	0.0879	0.7132	0.6856	46.6327
22	-1.50	0.00	0.0451	0.0009	-0.0008	0.0002	0.0000	0.1319	0.0733	0.0586	0.0852	0.6729	0.6830	46.6343
23	-2.00	0.00	0.0623	0.0012	-0.0005	0.0002	0.0000	0.1324	0.0733	0.0586	0.0852	0.7400	0.6820	46.6323
24	-3.00	0.00	0.0945	0.0017	-0.0003	0.0002	0.0000	0.1338	0.0739	0.0585	0.0836	0.7085	0.6806	46.6329
25	-4.00	0.00	0.1323	0.0022	-0.0006	0.0002	0.0000	0.1352	0.0747	0.0591	0.0836	0.6885	0.6794	46.6351
26	-5.00	0.00	0.1701	0.0026	-0.0005	0.0002	0.0000	0.1352	0.0748	0.0591	0.0826	0.6881	0.6790	46.6316
27	-6.00	0.00	0.2114	0.0031	-0.0004	0.0002	0.0000	0.1365	0.0755	0.0601	0.0815	0.6812	0.6784	46.6328
28	-7.00	0.00	0.2554	0.0037	-0.0003	0.0002	0.0000	0.1376	0.0777	0.0606	0.0802	0.6808	0.6789	46.6331
29	-8.00	0.00	0.3052	0.0042	-0.0008	0.0002	0.0000	0.1391	0.0781	0.0610	0.0804	0.6531	0.6793	46.6328
30	-9.00	0.00	0.3592	0.0049	-0.0000	0.0002	0.0000	0.1402	0.0784	0.0619	0.0802	0.6130	0.6798	46.6311
31	-10.00	0.00	0.4171	0.0057	-0.0002	0.0002	0.0000	0.1424	0.0790	0.0634	0.0803	0.6195	0.6805	46.6317
32	-11.00	0.00	0.4788	0.0066	0.0000	0.0002	0.0000	0.1449	0.0795	0.0654	0.0803	0.6139	0.6808	46.6303
33	-11.21	0.00	0.4911	0.0068	0.0001	0.0002	0.0000	0.1455	0.0795	0.0660	0.0803	0.4501	0.6809	46.6338

Sample Tabulated Data: Body Axis Data

ARG, INC. - AEDC DIVISION  
A SVERDRUP CORPORATION COMPANY  
VON KARMAN GAS DYNAMICS FACILITY  
ARNOLD AIR FORCE STATION, TENNESSEE  
STANDARD FORCE CONE (5 DEG)  
PAGE 2

DATE COMPUTED 31-AUG-79  
TIME COMPUTED 11:04:53  
DATE RECORDED 30-APR-78  
TIME RECORDED 20:23:31  
PROJECT NUMBER 641A-07

RUN CODE M PT TT Q P T RE REF LENGTHS(CUM,CUM,CUM)  
502 4 4.02 46.98 599.7 3.408 0.301 141.7 0.367E+07 28.274 34.290 34.290 34.290

CONFIG  
N12.5-106R-70-80

BODY AXIS-XMRP = (1/2) LM

PH	ALPHA	BETA	PHI	CM	CLM	CY	CLN	CLL	CAT	CAR	CA	MCP/LM	TCP/LM	A.C.	TRD
1	11.80	0.01	0.02	0.5261	-0.0938	-0.0038	0.0009	0.0000	0.1478	0.0794	0.0685	0.6821	0.6956	0.6817	46.6385
2	11.00	0.00	0.01	0.4863	-0.0886	-0.0037	0.0009	0.0000	-0.1457	0.0794	0.0644	0.6822	0.7033	0.6819	46.6364
3	10.00	0.00	0.02	0.4256	-0.0775	-0.0033	0.0008	0.0000	0.1431	0.0791	0.0640	0.6823	0.6997	0.6823	46.6350
4	9.00	0.00	0.00	0.3657	-0.0647	-0.0029	0.0007	0.0000	0.1410	0.0785	0.0625	0.6820	0.7020	0.6826	46.6364
5	8.00	-0.00	0.00	0.3122	-0.0568	-0.0030	0.0008	0.0000	0.1394	0.0781	0.0613	0.6820	0.7068	0.6823	46.6385
6	7.00	0.00	0.02	0.2629	-0.0478	-0.0024	0.0007	0.0000	0.1378	0.0777	0.0609	0.6820	0.6989	0.6815	46.6354
7	6.00	0.00	0.01	0.2160	-0.0393	-0.0020	0.0006	0.0000	0.1367	0.0774	0.0604	0.6822	0.7038	0.6810	46.6346
8	5.00	0.00	0.02	0.1751	-0.0319	-0.0018	0.0005	0.0000	0.1352	0.0765	0.0602	0.6826	0.7269	0.6807	46.6330
9	4.00	-0.00	0.00	0.1365	-0.0250	-0.0016	0.0005	0.0000	0.1336	0.0756	0.0596	0.6833	0.7293	0.6815	46.6331
10	3.00	0.00	0.02	0.1004	-0.0184	-0.0013	0.0005	0.0000	0.1321	0.0748	0.0589	0.6839	0.7309	0.6815	46.6320
11	2.00	-0.00	0.01	0.0659	-0.0121	-0.0010	0.0004	0.0000	0.1310	0.0740	0.0581	0.6848	0.7337	0.6829	46.6325
12	1.50	-0.00	0.01	0.0496	-0.0092	-0.0013	0.0004	0.0000	0.1301	0.0735	0.0583	0.6857	0.7144	0.6843	46.6355
13	1.00	-0.00	0.02	0.0336	-0.0062	-0.0010	0.0004	0.0000	0.1316	0.0733	0.0583	0.6857	0.7138	0.6849	46.6324
14	0.75	-0.00	0.02	0.0261	-0.0048	-0.0011	0.0004	0.0000	0.1314	0.0731	0.0584	0.6864	0.7006	0.6855	46.6316
15	0.50	-0.00	0.02	0.0176	-0.0032	-0.0012	0.0004	0.0000	0.1314	0.0731	0.0584	0.6864	0.6887	0.6857	46.6322
16	0.25	-0.00	0.01	0.0091	-0.0017	-0.0013	0.0004	0.0000	0.1315	0.0731	0.0584	0.6817	0.7146	0.6862	46.6326
17	0.00	-0.00	0.00	0.0020	-0.0003	-0.0010	0.0004	0.0000	0.1315	0.0732	0.0584	0.6817	0.7146	0.6862	46.6326
18	-0.25	-0.00	0.01	-0.0053	0.0010	-0.0009	0.0004	0.0000	0.1315	0.0734	0.0582	0.6812	0.7179	0.6876	46.6318
19	-0.50	-0.00	0.01	-0.0125	0.0024	-0.0008	0.0004	0.0000	0.1315	0.0734	0.0582	0.6812	0.7179	0.6876	46.6318
20	-0.75	-0.00	0.01	-0.0213	0.0041	-0.0008	0.0004	0.0000	0.1315	0.0734	0.0582	0.6812	0.7179	0.6876	46.6318
21	-1.00	-0.00	0.00	-0.0289	0.0055	-0.0010	0.0004	0.0000	0.1318	0.0732	0.0580	0.6812	0.7179	0.6876	46.6318
22	-1.50	-0.00	0.01	-0.0451	0.0084	-0.0008	0.0003	0.0000	0.1318	0.0732	0.0580	0.6812	0.7179	0.6876	46.6318
23	-2.00	-0.00	0.01	-0.0623	0.0116	-0.0008	0.0003	0.0000	0.1324	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
24	-3.00	-0.00	0.00	-0.0945	0.0178	-0.0005	0.0003	0.0000	0.1324	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
25	-4.00	-0.00	0.00	-0.1323	0.0242	-0.0006	0.0003	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
26	-5.00	-0.00	0.00	-0.1701	0.0308	-0.0005	0.0003	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
27	-6.00	-0.00	0.00	-0.2114	0.0369	-0.0005	0.0003	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
28	-7.00	-0.00	0.00	-0.2554	0.0422	-0.0003	0.0002	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
29	-8.00	-0.00	0.01	-0.3022	0.0451	-0.0004	0.0002	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
30	-9.00	-0.00	0.02	-0.3522	0.0448	-0.0004	0.0002	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
31	-10.00	-0.00	0.00	-0.4112	0.0418	-0.0002	0.0002	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
32	-11.00	-0.00	0.00	-0.4742	0.0364	0.0000	0.0002	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318
33	-11.21	-0.00	0.00	-0.4911	0.0286	0.0001	0.0002	0.0000	0.1325	0.0733	0.0585	0.6812	0.7179	0.6876	46.6318

Sample Tabulated Data: Body Axis Data

DATE COMPUTED 31-AUG-79  
TIME COMPUTED 11:04:54  
DATE RECORDED 30-APR-79  
TIME RECORDED 20:25:31  
PROJECT NUMBER V61A-07

ARM, INC. - AEDC DIVISION  
A SVERDRUP CORPORATION COMPANY  
VON KAPLAN GAS DYNAMICS FACILITY  
ARNOLD AIR FORCE STATION, TENNESSEE  
STANDARD FORCE CONE (5 DEG)  
PAGE 3

RUN CODE M PT TT Q P T RE A REF LENGTHS(CLM,CLM,CLL)  
502 4 4.02 46.98 599.7 3.408 0.301 141.7 0.367E+07 28.274 34.290 34.290

CONFIG  
N12.5-T06R-70-80

MISSILE AXIS-TMRP = (2/3) LM

PN	ALPHA	BETA	PMI	ALPP	CWP	CLMP	CYP	CLMP	CLLP	CAP	MCPP/LM	YCPP/LM	A.C.P	TIL
1	11.60	0.01	0.02	11.60	0.5261	-0.0081	-0.0036	0.0003	0.0000	0.1478	0.6821	0.6965	0.6817	46.6385
2	11.00	0.00	0.01	11.00	0.4863	-0.0075	-0.0036	0.0003	0.0000	0.1457	0.6822	0.7039	0.6819	46.6364
3	10.00	0.00	0.02	10.00	0.4256	-0.0066	-0.0032	0.0003	0.0000	0.1431	0.6823	0.7003	0.6823	46.6358
4	9.00	0.00	0.00	9.00	0.3657	-0.0056	-0.0028	0.0003	0.0000	0.1410	0.6820	0.7021	0.6826	46.6364
5	8.00	0.00	0.00	8.00	0.3122	-0.0048	-0.0023	0.0003	0.0000	0.1394	0.6820	0.7068	0.6823	46.6385
6	7.00	0.00	0.02	7.00	0.2629	-0.0040	-0.0019	0.0002	0.0000	0.1378	0.6820	0.6996	0.6815	46.6354
7	6.00	0.00	0.01	6.00	0.2160	-0.0033	-0.0018	0.0002	0.0000	0.1352	0.6822	0.7044	0.6810	46.6344
8	5.00	0.00	0.02	5.00	0.1751	-0.0027	-0.0016	0.0003	0.0000	0.1326	0.6826	0.7280	0.6807	46.6330
9	4.00	0.00	0.00	4.00	0.1345	-0.0022	-0.0015	0.0003	0.0000	0.1301	0.6833	0.7294	0.6810	46.6331
10	3.00	0.00	0.02	3.00	0.1004	-0.0017	-0.0010	0.0003	0.0000	0.1276	0.6839	0.7320	0.6815	46.6320
11	2.00	0.00	0.01	2.00	0.0659	-0.0011	-0.0009	0.0002	0.0000	0.1251	0.6848	0.7344	0.6829	46.6325
12	1.50	0.00	0.01	1.50	0.0456	-0.0009	-0.0007	0.0002	0.0000	0.1221	0.6860	0.7178	0.6843	46.6335
13	1.00	0.00	0.01	1.00	0.0336	-0.0004	-0.0005	0.0002	0.0000	0.1214	0.6857	0.7146	0.6855	46.6324
14	0.75	0.00	0.02	0.50	0.0216	-0.0003	-0.0012	0.0002	0.0000	0.1214	0.6864	0.7007	0.6849	46.6315
15	0.50	0.00	0.01	0.25	0.0091	-0.0002	-0.0013	0.0002	0.0000	0.1214	0.6867	0.7157	0.6855	46.6316
16	0.25	0.00	0.00	0.00	0.0020	0.0000	-0.0010	0.0002	0.0000	0.1216	0.6817	0.7146	0.6857	46.6332
17	0.00	0.00	0.00	0.00	0.0000	0.0001	-0.0009	0.0002	0.0000	0.1216	0.6842	0.7178	0.6876	46.6318
18	-0.25	0.00	0.01	-0.25	-0.0053	0.0003	-0.0009	0.0002	0.0000	0.1215	0.6856	0.7171	0.6879	46.6337
19	-0.50	0.00	0.00	-0.50	-0.0123	0.0005	-0.0004	0.0002	0.0000	0.1216	0.6879	0.7115	0.6872	46.6335
20	-0.75	0.00	0.01	-0.75	-0.0213	0.0005	-0.0010	0.0002	0.0000	0.1218	0.6879	0.7112	0.6856	46.6327
21	-1.00	0.00	0.00	-1.00	-0.0289	0.0007	-0.0009	0.0002	0.0000	0.1219	0.6852	0.6730	0.6830	46.6343
22	-1.50	0.00	0.01	-1.50	-0.0451	0.0009	-0.0005	0.0002	0.0000	0.1224	0.6836	0.7395	0.6820	46.6323
23	-2.00	0.00	0.00	-2.00	-0.0623	0.0012	-0.0005	0.0002	0.0000	0.1238	0.6826	0.7082	0.6806	46.6329
24	-3.00	0.00	0.00	-3.00	-0.0965	0.0017	-0.0008	0.0002	0.0000	0.1352	0.6826	0.6894	0.6794	46.6351
25	-4.00	0.00	0.00	-4.00	-0.1323	0.0022	-0.0008	0.0002	0.0000	0.1365	0.6816	0.6881	0.6790	46.6316
26	-5.00	0.00	0.00	-5.00	-0.1701	0.0026	-0.0004	0.0002	0.0000	0.1376	0.6812	0.7056	0.6788	46.6328
27	-6.00	0.00	0.00	-6.00	-0.2114	0.0031	-0.0003	0.0002	0.0000	0.1383	0.6808	0.7134	0.6789	46.6331
28	-7.00	0.00	0.00	-7.00	-0.2554	0.0037	-0.0009	0.0002	0.0000	0.1401	0.6804	0.6572	0.6791	46.6328
29	-8.00	0.00	0.01	-8.00	-0.3052	0.0042	-0.0001	0.0002	0.0000	0.1424	0.6803	0.6282	0.6798	46.6317
30	-9.00	0.00	0.02	-9.00	-0.3552	0.0048	-0.0002	0.0002	0.0000	0.1449	0.6803	0.5285	0.6808	46.6302
31	-10.00	0.00	0.00	-10.00	-0.4171	0.0057	0.0000	0.0002	0.0000	0.1455	0.6803	0.4844	0.6809	46.6338
32	-11.00	0.00	0.00	-11.00	-0.4788	0.0066	0.0000	0.0002	0.0000	0.1455	0.6803	0.4844	0.6809	46.6338
33	-11.21	0.00	0.00	-11.21	-0.4911	0.0068	0.0002	0.0002	0.0000	0.1455	0.6803	0.4844	0.6809	46.6338

Sample Tabulated Data: Missile Axis Data

DATE COMPUTED 31-AUG-79  
 TIME COMPUTED 11:04:52  
 DATE RECORDED 30-APR-79  
 TIME RECORDED 20:25:31  
 PROJECT NUMBER V41A-07

ARO, INC. - AEDC DIVISION  
 A SVERDRUP CORPORATION COMPANY  
 VON KARMAN GAS DYNAMICS FACILITY  
 ARNOLD AIR FORCE STATION, TENNESSEE  
 STANDARD FORCE CONE (5 DEG)  
 PAGE 4

RUN CODE		M	PT	TT	O	P	T	RE	A REF LENGTHS(CLN-CLN,CLL)			
502	4	4.02	46.98	599.7	3.408	0.301	141.7	0.367E+07	28.274	34.290	34.290	34.290
CONFIG												
M12.5-T06R-F0-R0												
PH	ALPI	PHIZ	PT	TT	O	P	T	RE	P81/P	P82/P	P83/P	P84/P
1	11.08	0.02	46.98	599.7	3.408	0.301	0.0744	0.1022	0.1022	0.1022	0.1022	0.1022
2	10.51	0.01	46.98	599.7	3.408	0.301	0.0794	0.1020	0.1020	0.1020	0.1020	0.1020
3	9.34	0.01	46.91	599.7	3.403	0.301	0.0791	0.1054	0.1054	0.1054	0.1054	0.1054
4	8.37	0.00	47.01	599.7	3.411	0.302	0.0785	0.1119	0.1119	0.1119	0.1119	0.1119
5	7.61	0.00	46.95	599.7	3.406	0.301	0.0761	0.1163	0.1163	0.1163	0.1163	0.1163
6	6.83	0.02	46.94	599.7	3.409	0.301	0.0777	0.1205	0.1205	0.1205	0.1205	0.1205
7	5.66	0.01	46.95	599.7	3.406	0.301	0.0774	0.1246	0.1246	0.1246	0.1246	0.1246
8	4.68	0.01	46.95	599.7	3.406	0.301	0.0765	0.1343	0.1343	0.1343	0.1343	0.1343
9	3.70	0.00	47.01	599.7	3.410	0.301	0.0756	0.1445	0.1445	0.1445	0.1445	0.1445
10	2.73	0.02	46.94	599.7	3.408	0.301	0.0748	0.1544	0.1544	0.1544	0.1544	0.1544
11	1.74	0.01	46.97	599.7	3.408	0.301	0.0740	0.1634	0.1634	0.1634	0.1634	0.1634
12	1.25	0.00	46.92	599.7	3.404	0.301	0.0735	0.1682	0.1682	0.1682	0.1682	0.1682
13	0.76	0.01	46.99	599.7	3.409	0.301	0.0733	0.1713	0.1713	0.1713	0.1713	0.1713
14	0.52	0.02	46.99	599.7	3.409	0.301	0.0731	0.1729	0.1729	0.1729	0.1729	0.1729
15	0.27	0.02	46.95	599.7	3.406	0.301	0.0731	0.1736	0.1736	0.1736	0.1736	0.1736
16	0.03	0.01	46.92	599.7	3.404	0.301	0.0731	0.1732	0.1732	0.1732	0.1732	0.1732
17	-0.22	0.00	46.87	599.7	3.400	0.301	0.0732	0.1719	0.1719	0.1719	0.1719	0.1719
18	-0.47	0.01	46.97	599.7	3.407	0.301	0.0734	0.1700	0.1700	0.1700	0.1700	0.1700
19	-0.71	-0.00	47.01	599.7	3.410	0.301	0.0734	0.1695	0.1695	0.1695	0.1695	0.1695
20	-0.96	0.01	46.94	599.7	3.406	0.301	0.0734	0.1702	0.1702	0.1702	0.1702	0.1702
21	-1.21	0.00	46.98	599.7	3.408	0.301	0.0733	0.1721	0.1721	0.1721	0.1721	0.1721
22	-1.70	0.00	46.96	599.7	3.407	0.301	0.0733	0.1707	0.1707	0.1707	0.1707	0.1707
23	-2.19	0.00	46.91	599.7	3.403	0.301	0.0739	0.1642	0.1642	0.1642	0.1642	0.1642
24	-2.17	0.00	46.98	599.7	3.408	0.301	0.0747	0.1554	0.1554	0.1554	0.1554	0.1554
25	-2.15	0.00	47.02	599.7	3.411	0.302	0.0756	0.1452	0.1452	0.1452	0.1452	0.1452
26	-2.13	0.00	46.91	599.7	3.403	0.301	0.0765	0.1349	0.1349	0.1349	0.1349	0.1349
27	-2.10	-0.00	47.00	599.7	3.410	0.301	0.0773	0.1259	0.1259	0.1259	0.1259	0.1259
28	-2.08	0.00	47.00	599.7	3.409	0.301	0.0777	0.1206	0.1206	0.1206	0.1206	0.1206
29	-2.05	0.01	47.01	599.7	3.410	0.301	0.0781	0.1168	0.1168	0.1168	0.1168	0.1168
30	-2.02	0.02	46.94	599.7	3.409	0.301	0.0784	0.1131	0.1131	0.1131	0.1131	0.1131
31	-1.99	0.00	46.98	599.7	3.408	0.301	0.0790	0.1065	0.1065	0.1065	0.1065	0.1065
32	-1.95	-0.00	46.95	599.7	3.406	0.301	0.0795	0.1007	0.1007	0.1007	0.1007	0.1007
33	-1.91	-0.00	46.92	599.7	3.404	0.301	0.0795	0.1005	0.1005	0.1005	0.1005	0.1005
TORC				-11.0 TORC	-7.0							

Sample Tabulated Data: Tunnel Conditions Data